

REQUEST FOR QUOTE
Pascagoula Veterans and Shortcut Drainage Project

SCOPE OF WORK

The scope of work includes the installation of 190 LF of 22" X 13" reinforced concrete arch pipe and end sections, regrading of approximately 600 LF of existing ditch, and removal and replacement of sidewalk, curb, asphalt pavement, and striping as shown on the plans.

Tasks:

- Prior to start of work, Contractor shall provide and place construction signs, at a minimum, as shown on sheet TTC-1 of the plans. Signage will include channelization devices, "Road Work Ahead" signs, "End Road Work" signs, "Lane Ends" sign, and road closure barricades.
- Saw cut and remove existing pavement and concrete only to the limits shown on the plans.
- Install drainage pipe to the grades shown on the plans.
- Install conflict box on drainage pipe, if needed, in order to work around existing utilities.
- Compact soil in roadway or driveway areas in lifts not to exceed 6".
- Before installing concrete or asphalt drives, check for stability using a loaded truck, remove any soft spots that "pump" and recompact until all areas are stable.
- Replace reinforced concrete driveway. Epoxy dowel bars into existing concrete and install concrete reinforcement prior to pouring concrete.
- Place 3" of asphalt pavement base course (1 lift) and 3" of asphalt pavement surface course (placed in 2-1.5" lifts) to match thickness and width of existing pavement. Roll to refusal.
- Regrade existing ditch to the grades shown on the plans.
- Remove all traffic control devices after completion of the work.
- Contractor shall accommodate local traffic to the best of his ability.
- Contractor shall coordinate relocation of affected utilities with respective utility owners.

Notes:

- Any work items necessary to complete the construction as specified above and not listed shall be considered incidental to the other items of work shown herein.
- Contractor is to locate and pothole all existing utilities that may be in conflict with the work and report locations and elevations to the Engineer prior to continuing with the work.
- Contractor is responsible for erosion control and compliance with all local, state, and federal rules and regulations.
- All work is to be performed in accordance with (Current) Manual of Uniform Traffic Control Devices and 2004 Mississippi Standard Specifications for Road and Bridge Construction.
- Closures on the Walmart concrete driveway are to be coordinated with the store's management at least 72 hours prior to start of work.
- Work is to be completed within 30 days of execution of Contract.
- The City of Pascagoula will be responsible for adjustments of water lines as necessary to accomplish the work.

Veterans Ave/Shortcut Rd Drainage

Quote Form

Pay Item	Item Description	Unit	Quantity	Unit Price	Extension
1	Mobilization	LS	1		
2	Maintenance of Traffic	LS	1		
3	Establishment of Vegetation	LS	1		
4	Removal of Drainage Culvert (All Types & Sizes)	LF	40		
5	22" X 13" Reinforced Concrete Arch Pipe, Class III	LF	192		
6	22" X 13" Reinforced Concrete Arch Pipe End Section, Class III	EA	3		
7	Select Backfill (Class B5)	CY	40		
8	Base Material (Size 610 Crushed Stone)	CY	20		
9	Concrete Sidewalk, 4 inch min.	SY	10		
10	Removal and Replacement of Concrete Curb and Gutter	LF	25		
11	Removal and Replacement of Concrete Curb	LF	50		
12	Asphalt Pavement, Base Course (3")	TON	10		
13	Asphalt Pavement, Surface Course (3")	TON	10		
14	Concrete Driveway, 6 in min., Reinforced	CY	12		
15	Excess Excavation	CY	65		
16	Saw Cutting (Asphalt & Concrete)	LF	265		
17	Thermoplastic Pavement Marking	LS	1		
18	Wattles	LF	40		
19	Tie to Existing Curb Inlet	LS	1		
20	Class "B" Structural Concrete	CY	7		
21	Reinforcing Steel	LB	315		
22	Manhole Lid and Frame	EA	1		
TOTAL CONSTRUCTION COST :					

Respectfully submitted by: _____
(Contractor's Construction Company Submitting Quote)

Signature: _____ Title: _____
(Authorized Representative)

Printed Name: _____

Address: _____

Phone Number: _____