



















TRANSITION PLAN

ITEM #	LOCATION	SECTION #: GROUP	NON-COMPLIANCE DESCRIPTION	COMMENTS / SUGGESTED CORRECTIONS	PRIORITY	COST CODE	BUDGET COST	COMPL. DATE	PHOTOGRAPHS
1	Sta. 12+50 East Taylor Ave. @ 9th St. (SE corner)	R207: Curb Ramps	1. No curb ramp 2. Landing/turning space	1. Provide curb ramp.	1	CR4	\$ 750		
2	Sta. 12+50 to 16+25 East Taylor Ave. intersecting 9th to 10th St. (South side of street)	R204.2: Sidewalks	1. Cross slope > 2% 2. Vertical alignment > 1/4" 3. Vegetation/grass encroachment 4. Sidewalk width < 5'-0"	1. Remove and replace sidewalk. (±351 L.F.) 2. Remove and replace drive ramps. (2) 3. Coordinate utility and signage locations. (Not included in Budget Costs) 4. Remove vegetation/grass encroachment.	3	SW1 DR1	\$ 23,550		
3	Sta. 16+25 East Taylor Ave. intersecting 10th St. (SW corner)	R207: Curb Ramps	1. Curb ramp width < 5'-0" 2. Landing/turning space	1. Remove and replace curb ramp. 2. Coordinate drainage locations. (Not included in Budget Costs)	1	CR4	\$ 750		
4	Sta. 16+25 East Taylor Ave. @ 10th St. (SE corner)	R207: Curb Ramps	1. Curb ramp width < 5'-0"	1. Remove and replace curb ramp. 2. Coordinate drainage and utility locations. (Not included in Budget Costs)	1	CR2B	\$ 1,000		
5	Sta. 16+25 to 20+00 East Taylor Ave. intersecting 10th to 11th St. (South side of street)	R204.2: Sidewalks	1. Cross slope > 2% 2. Vertical alignment > 1/4" 3. Vegetation/grass encroachment 4. Sidewalk width < 5'-0"	1. Remove and replace sidewalk. (±351 L.F.) 2. Remove and replace drive ramps. (2) 3. Remove vegetation/grass encroachment.	3	SW1 DR1	\$ 23,550		
6	Sta. 20+00 East Taylor Ave. @ 11th St. (SW corner)	R207: Curb Ramps	1. Curb ramp width < 5'-0"	1. Remove and replace curb ramp.	1	CR4	\$ 750		



TRANSITION PLAN

ITEM #	LOCATION	SECTION #: GROUP	NON-COMPLIANCE DESCRIPTION	COMMENTS / SUGGESTED CORRECTIONS	PRIORITY	COST CODE	BUDGET COST	COMPL. DATE	PHOTOGRAPHS
7	Sta. 20+00 East Taylor Ave. @ 11th St. (SE corner)	R207: Curb Ramps	1. Curb ramp width 5'-0"	1. Remove and replace curb ramp.	1	CR4	\$ 750		
8	Sta. 20+00 to 22+00 East Taylor Ave. intersecting 11th St. (south side of street)	R204.2: Sidewalks	1. Cross slope > 2% 2. Vertical alignment > 1/4" 3. Vegetation/grass encroachment 4. Sidewalk width < 5'-0"	1. Remove and replace sidewalk. (±212 L.F.) 2. Remove and replace drive ramps. (1) 3. Coordinate drainage, utilities and signage locations. (Not included in Budget Costs) 4. Remove vegetation/grass encroachment.	3	SW1 DR1	\$ 13,600		
9	Sta. 22+00 East Taylor Ave. @ 11th St. (South)	R207: Curb Ramps	1. Curb ramp width < 5'-0"	1. Remove and replace curb ramp. 2. Poor drainage. (Not included in Budget Costs)	1	CR3	\$ 700		
10	Sta. 22+00 East Taylor Ave. @ 11th St. (NE corner)	R207: Curb Ramps	1. Vertical alignment > 1/4 " at bottom of ramp	1. Repair brick detectable warning surface.	1		\$ 150		
11	Sta. 22+00 to 23+50 East Taylor Ave. (south side of street to 12th St.)	R204.2: Sidewalks	1. Sidewalk width < 5'-0"	1. Remove and replace sidewalk. (±150 L.F.) 2. Coordinate drainage, utilities and signage locations. (Not included in Budget Costs)	3	SW1	\$ 7,500		
12	Sta. 22+00 to 30+75 East Taylor Ave., intersecting streets are 11th St. and 14th St. (north side of street)	R204.2: Sidewalks	1. Sidewalk width < 5'-0" 2. Cross slope > 2% 3. Vertical alignment > 1/4" 4. Vegetation/grass encroachment	1. Remove and replace sidewalk. (±720 L.F.) 2. Remove and replace drive ramps (1). 3. Remove vegetation/grass encroachment.	3	SW1 DR4	\$ 38,950		

TRANSITION PLAN

ITEM #	LOCATION	SECTION #: GROUP	NON-COMPLIANCE DESCRIPTION	COMMENTS / SUGGESTED CORRECTIONS	PRIORITY	COST CODE	BUDGET COST	COMPL. DATE	PHOTOGRAPHS
13	Sta. 23+50 East Taylor Ave. @ 12th St. (SW corner)	R207: Curb Ramps	1. Curb ramp width < 5'-0" 2. Running slope > 8.33% 3. Cross slope > 2% 4. Vertical alignment > 1/4" at bottom of ramp	1. Remove and replace curb ramp. 2. Poor drainage. (Not included in Budget Costs)	1	CR4	\$ 750		
14	Sta. 23+50 East Taylor Ave. @ 12th St. (SE corner)	R207: Curb Ramps	1. Curb ramp width < 5'-0" 2. Vertical alignment > 1/4"	1. Remove and replace curb ramp. 2. Poor drainage. (Not included in Budget Costs)	1	CR1C	\$ 1,000		
15	Sta. 23+50 to 27+25 East Taylor Ave. (south side of street intersecting 12th St. to 13th St.)	R204.2: Sidewalks	1. Sidewalk width < 5'-0" 2. Cross slope > 2% 3. Vertical alignment > 1/4" at drive ramp	1. Remove and replace sidewalk. (±361 L.F.) 2. Remove and replace drive ramps. (1) 3. Coordinate drainage, ROW and signage locations. (Not included in Budget Costs)	3	SW1 DR1	\$ 21,050		
16	Sta. 27+25 East Taylor Ave. @ 13th St. (SW corner)	R207: Curb Ramps	1. Curb ramp width < 5'-0" 2. Cross slope > 2% 3. Vertical alignment > 1/4" at drive ramp	1. Remove and replace curb ramp.	1	CR4A	\$ 750		
17	Sta. 27+25 East Taylor Ave. @ 13th St. (SE corner)	R207: Curb Ramps	1. Curb ramp width < 5'-0" 2. Vertical alignment > 1/4" at bottom of ramp	1. Remove and replace curb ramp. 2. Poor drainage. (Not included in Budget Costs)	1	CR2C	\$ 1,000		
18	Sta. 27+25 to 30+75 East Taylor Ave., intersecting streets are 13th St. to 14th St. (south side of street)	R204.2: Sidewalks	1. Sidewalk width < 5'-0" 2. Cross slope > 2% 3. Vertical alignment > 1/4" 4. Vegetation/grass encroachment	1. Remove and replace sidewalk. (±338 L.F.) 2. Remove and replace drive ramps. (1) 3. Coordinate drainage, ROW and signage locations. (Not included in Budget Costs) 4. Remove vegetation/grass encroachment.	3	SW1 DR1	\$ 19,900		

**TRANSITION PLAN**

ITEM #	LOCATION	SECTION #: GROUP	NON-COMPLIANCE DESCRIPTION	COMMENTS / SUGGESTED CORRECTIONS	PRIORITY	COST CODE	BUDGET COST	COMPL. DATE	PHOTOGRAPHS
19	Sta. 30+75 East Taylor Ave. (south side of street)	R207: Curb Ramps	1. No curb ramp 2. No crosswalk markings	1. Provide curb ramp (N-S). 2. Provide crosswalk (N-S). 3. Provide crosswalk markings.	1	CR3D CW1	\$ 1,700		
20	Sta. 30+75 East Taylor Ave. (north side of street)	R207: Curb Ramps	1. No curb ramp	1. Provide curb ramp (N-S). 2. See item 17 for crosswalk.	1	CR2	\$ 650		

**PLAN TOTAL: \$ 158,800**